

## Indianapolis Power & Light Company Harding Street Generating Station

Ash Pond System Emergency Action Plan for CCR Rule Compliance

Prepared by



55 East Monroe Street Chicago, IL 60603-5780 USA 312-269-2000 www.sargentlundy.com

> Project No. 10572-088 Report No. SL-013824

> > Rev. 0

Issue Date: March 31, 2017 Issue Purpose: For Use



### **LEGAL NOTICE**

This report ("Deliverable") was prepared by Sargent & Lundy, L.L.C. ("S&L"), expressly for the sole use of Indianapolis Power & Light Company ("Client") in accordance with the agreement between S&L and Client. This Deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this Deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of the Client; (2) information and data provided by others may not have been independently verified by S&L; and (3) the information and data contained in this Deliverable are time sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this Deliverable. Any use or reliance upon this Deliverable by third parties shall be at their sole risk.

Issue



Report No. SL-013824 Project No. 10572-088 Rev. 0 March 31, 2017

Pages

# INDIANAPOLIS POWER & LIGHT COMPANY HARDING STREET GENERATING STATION ASH POND SYSTEM EMERGENCY ACTION PLAN

### **ISSUE SUMMARY & CERTIFICATION**

This is to confirm that this report has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Rev.	<u>Purpose</u>	Issue Date	Prepared By	Reviewed By	Approved By	Affected
0	Use	03/31/2017	T. Dehlin	D. Nielson	P. Miner	All
			th Dehlo	In	P.s.m-	_
	I certify that thi	s emergency act	ion plan meets the rec	quirements of 40 CFR 2.	57.73(a)(3).	
			repared by me or und laws of the State of I	der my direct supervision diana.	on and that I am a regi	stered
	Certified By:	S/s.	2	Date:	3-31-17	
	Seal:	PE10	3-31-17 	18		




FIGURE i



### SUMMARY OF EMERGENCY ACTION PLAN PROCESS

There are four steps that must be followed anytime an incident or emergency event is detected at the Harding Street Generating Station – Ash Pond System. The steps are:

Step 1: Event Detection and Level Determination

Step 2: Notification and Communication

Step 3: Expected Actions

Step 4: Termination and Follow-up

Incidents and emergency events are defined in Section 1.2.1 of this Emergency Action Plan (EAP). Specific actions required for each step will depend on the severity of the situation as defined during Step 1. The actions required for each step of the EAP are summarized graphically on the EAP Flow Chart (Figure i) and are described in the corresponding EAP Section. A summary of each step is provided below.

### **Step 1 - Event Detection and Level Determination**

During the initial step, an incident or emergency event is detected within the Ash Pond System and classified by the EAP Coordinator (or designee) into one of the following event levels:

Event Level 3: Incident, slowly developing

Event Level 2: Emergency Event, rapidly developing

Event Level 1: Emergency Event, imminent dike failure or flash flooding

Information to help the EAP Coordinator (or designee) determine which of the above event levels is applicable is provided in Section 1 of this EAP.

### **Step 2 - Notification and Communication**

After the event level has been determined, notifications are made in accordance with the appropriate notification flow chart provided in Section 2 of this EAP.

### **Step 3 - Expected Actions**

After the initial notifications are made, the EAP Coordinator (or designee) should refer to Table 3.1 and confer with the Engineering Director (or designee) to develop and execute appropriate preventative actions. During this step of the EAP, there is a continuous process of taking actions, assessing the status of the situation, and keeping others informed through communication channels established during the initial notifications. The EAP may go through multiple event levels during Steps 2 and 3 as the situation either improves or worsens.

### Step 4 - Termination and Follow-Up

Once the event has ended or has been resolved, termination and follow-up procedures should be followed as outlined in Section 4 of this EAP. EAP operations can only be terminated after completing operations under Event Level 3 or 1. If Event Level 2 is declared, the operations must be designated Event Level 3 or 1 before terminating the EAP operations.



### TABLE OF CONTENTS

### PRELIMINARY PAGES EMERGENCY ACTION PLAN FLOW CHART ......iii TABLE OF CONTENTS ......v PURPOSE vii ASH POND SYSTEM ......vii EAP ANNUAL REVIEW AND PERIODIC TEST......vii REVISIONS .......viii SECTION 1. EVENT DETECTION AND LEVEL DETERMINATION......1-1 1.2.2 Level Determination 1-2 1.2.3 Level Determination Guidance 1-2 SECTION 2. NOTIFICATION AND COMMUNICATION ......2-1 2.1 COMMUNICATION SYSTEMS ......2-1 2.2 SUGGESTED PRESCRIPTED MESSAGES FOR EAP COORDINATOR ......2-1 2.3 PUBLIC AFFAIRS PLAN 2-2 SECTION 3. EXPECTED ACTIONS......3-1 3.2 LOCALLY AVAILABLE EQUIPMENT, LABOR, AND MATERIALS......3-20 SECTION 4. TERMINATION AND FOLLOW-UP......4-1 4.1 TERMINATION RESPONSIBILITIES ......4-1 4.2 FOLLOW-UP.......4-1

SECTION 5. MAPS, FIGURES, AND SUPPORTING DATA .....5-1



### TABLE OF CONTENTS (CONT.)

TABLES	
Table 1.1 – Event Level Determination Guidance	1-3
Table 1.2 – Pond Dike Elevations and Maximum Surface Water Elevations	1-5
Table 3.1 – Action Data Sheet Index	3-1
FIGURES	
Figure i – Emergency Action Plan Flow Chart	iii
Figure 2.1 – Notification Flow Chart for Event Level 3	2-4
Figure 2.2 – Notification Flow Chart for Event Level 2	2-5
Figure 2.3 – Notification Flow Chart for Event Level 1	2-6
Figure 5.1 – Location and Vicinity Map	5-2
Figure 5.2 – Ash Pond System Layout Annotated Aerial Photograph	5-3
Figure 5.3 – Emergency Site Access Route Map	5-4
Figure 5.4 – Estimated Dike Breach Inundation Map	5-5
Figure 5.5 – Ash Pond System Area and Capacity Curves	5-6
FORMS	
Form 3.1 – Incident or Emergency Event Log	3-21
Form D.1 – Ash Pond System – EAP Annual Review Verification Statement	D-3
APPENDICES	
Appendix A – Warning and Evacuation	
Appendix B – Inundation Map Documentation	
Appendix C – Past EAP Activity	
Appendix D – EAP Review and Revision	
Appendix E – EAP Distribution	
Appendix F – Location of Supplementary Information	
Appendix G – Glossary	



### **PURPOSE**

The purpose of the EAP is to reduce the risk of human loss of life and injury during an incident or emergency event at the Harding Street Generating Station – Ash Pond System.

A secondary purpose of the EAP is to minimize the potential for property damage during an incident or emergency event at the Harding Street Generating Station – Ash Pond System. The intent of the EAP is to identify problems early and repair them before they result in failure of any of the dikes at the Harding Street Generating Station.

### **ASH POND SYSTEM**

The location and layout of the ash ponds and associated dikes at the Ash Pond System of the Harding Street Generating Station is shown on Figure 5.2. There are four active ash ponds at the station. The ponds are identified as Pond 1, Pond 2A, Pond 2B, and Pond 3. Former Ponds 2, 4, 4A and 4B were regraded prior to October 19, 2015 such that these former ponds can no longer impound water. Construction details of the perimeter dikes for these ponds are available on file in the EAP office at the station.

Coal ash produced as a byproduct of generating electricity is combined with water and then transported and discharged into the northwest portion of Pond 1, the station's initial ash settling pond. Ash particles are allowed to settle out on the floor of the pond as the water moves across the pond to the pond's outlet pipes. Processed water from Pond 1 is then transferred to Pond 2A/2B through a 30-inch-diameter corrugated metal pipe where the ash particles are allowed additional sedimentation time. The wastewater subsequently discharges from Pond 2A/2B into Pond 3 through a 24-inch-diameter culvert. Following final sedimentation of the finer waste constituents in Pond 3, the processed water discharges into a drop outlet structure (National Pollutant Discharge Elimination System-permitted Outfall 006) through three 12-inch-diameter welded steel pipes. An 18-inch-diameter reinforced concrete pipe then discharges the processed water into Lick Creek.

### EAP ANNUAL REVIEW AND PERIODIC TEST

This EAP document will require an annual review and update to stay current. A periodic test of the EAP procedures is also required every five years to ensure continued effectiveness. For annual review and revision procedures, see Appendix D.



### **REVISIONS**

For	ravigion	procedures	, see Appendix D	
гог	revision	procedures,	, see Appendix D	٠.

Revision No.	Date	Revisions Made	
0	03/31/2017	EAP published in IDNR 2012 format	

Revised pages inserted in this EAP by:	
	(Signature)
	(Printed Name)
	(
	(D.1.)
	(Date)



## SECTION 1. EVENT DETECTION AND LEVEL DETERMINATION

This section of the EAP describes the first step that must be followed whenever an incident or emergency event is detected at the Harding Street Generating Station – Ash Pond System. The layout and location of ash ponds and associated dikes for the Ash Pond System at the Harding Street Generating Station is shown on Figure 5.2. This section also describes event detection and information to assist the EAP Coordinator (or designee) in determining the appropriate level for the event.

### 1.1 EVENT DETECTION

Incidents or emergency events may be detected by various means including but not limited to the following:

- 1. Results of inspections.
- 2. Instrument readings on the dikes or in the plant.
- 3. Notification by local emergency services personnel, especially during a severe weather or other natural event such as an earthquake.
- 4. Notification by on-site employees.
- 5. Notification by off-site personnel or neighbors.

After any incident or emergency event is detected and reported to the EAP Coordinator, the EAP Coordinator (or Acting EAP Coordinator) is responsible for determining the level of the event. If the Local Emergency Services Agency receives a 911 call regarding observations of an incident or emergency event at the Ash Pond System, the dispatcher shall first contact the EAP Coordinator. The EAP Coordinator shall determine the appropriate event level (as defined in Section 1.2.2) and advise the dispatcher of the event level.

### 1.2 EVENT LEVEL DETERMINATION

### 1.2.1 Incidents and Emergency Events

An incident is defined as an event, which takes place, or a condition, which is slowly developing, that is not normally encountered in the routine operation of the Ash Pond System, or necessitates a variation from Standard Operating Procedures. Such events are more common than emergency conditions and often offer time to conduct preplanned responses to the slowly developing situation. If addressed in a timely manner, such events can often be prevented from progressing into a much worse event. An incident requires operations in accordance with Event Level 3 of this EAP.

An emergency event is defined as an event, which takes place, or a condition, which develops, that is of a serious nature that may endanger the dikes of the Ash Pond System, or endanger persons or property, and



demands immediate attention. An emergency event requires immediate operations in accordance with Event Level 2 or 1 of this EAP.

### 1.2.2 Level Determination

The EAP Coordinator shall be responsible for defining incidents or emergency events as one of the three following event levels:

**Event Level 3 -** This is an incident that is defined as a slowly developing situation that may endanger the structural integrity of the Ash Pond System dikes. This event level also involves a determination that it will be possible to retain the structural integrity of the Ash Pond System dikes and avoid release of fluids and ash.

**Event Level 2 -** This is an emergency event that is defined as rapidly developing and could quickly lead to dike failure and flash flooding downstream of the Ash Pond System. This event level also involves a determination that it may be possible to retain the structural integrity of the Ash Pond System dike and avoid release of fluids and ash beyond the perimeter of the existing dike involved. All decisions to prevent this occurrence must fully consider the safety of those involved in any repairs to be undertaken. If fluid levels within the ash pond in question cannot be reduced significantly to prevent release, the possibility of repair should not be considered.

**Event Level 1 -** This is an emergency event that is defined as imminent dike failure and the possibility of flash flooding downstream of the dike. This event may include the determination that it will not be possible to retain the structural integrity of the Ash Pond System dikes to avoid release of fluids and ash.

### 1.2.3 Level Determination Guidance

Table 1.1 shall be used as a guide for determining the appropriate event level. This table attempts to be all inclusive; however, an event or condition may arise that is not covered in this table. In the circumstance of multiple events occurring within the Ash Pond System with conflicting event levels, always designate the higher event level as the governing event level.

### 1.2.4 Roles, Responsibilities, and Authority

The EAP personnel for the Harding Street Generating Station Ash Pond System include the following:

- EAP Coordinator Designated Station Employee familiar with the Ash Pond System.
- Engineering Director Designated Station Engineer familiar with the Ash Pond System.
- Warning/Evacuation Director Local Fire or Police Department Employee familiar with Harding Street Generating Station and the Ash Pond System.
- Public Relations Director Designated IPL Employee trained to understand principal elements of this EAP.
- On-Call Engineer Registered Indiana Professional Engineer with special expertise and experience in geotechnical engineering and the design and operation of ash pond dikes.



The EAP Coordinator shall function as the EAP operations coordinator and/or Incident Manager during any of the three event levels of operation described in this EAP. The EAP Coordinator has the authority to take the necessary actions described in this EAP. As the situation requires and as time permits, the EAP Coordinator should consult with the Engineering Director before initiating notifications described in this EAP. In the case of Event Levels 2 and 1, the EAP Coordinator and Engineering Director should consult with the On-Call Engineer throughout the decision process regarding actions to be undertaken.

The EAP Coordinator is responsible for providing initial, timely, and accurate notifications to the Warning/Evacuation Director and the Public Relations Director after an Event Level 2 or 1 has been determined. The EAP Coordinator is also responsible for providing subsequent updates of the situation to the Warning/Evacuation Director to assist in making timely and accurate decisions regarding warning and evacuation responsibilities.

Once an Event Level 3 or 1 is terminated, the EAP Coordinator is responsible to submit to the Engineering Director, as soon as possible, an accurate summary document of the field observation and activities of the event.

The Warning/Evacuation Director is primarily responsible for coordinating the preparation to evacuate people downstream of the Harding Street Generating Station, as well as the implementation of the evacuation itself. Should an incident or emergency situation be detected by someone outside of the station, the Warning/Evacuation Director should notify the EAP Coordinator so that the EAP coordinator can then notify other interested parties.

The Engineering Director is responsible for assisting in technical aspects of the Ash Pond System dikes, event level determination and evaluation, and anything that pertains to the condition of the dikes within the Ash Pond System, including any necessary follow-up activities. The Engineering Director will also assist in performing annual reviews and issuing updates to this EAP.

TABLE 1.1 - EVENT LEVEL DETERMINATION GUIDANCE

Event	Observation	Event Level
Flooding and Overtopping	In the event of potential flooding, the water surface elevation of each pond would be observed using the installed staff gauges and compared to each Event Level's specified threshold, which was developed from the elevations provided in Table 1.2. For an Event Level 3 to be declared as a result of flooding, the pond water surface elevation, <i>h</i> , would be as follows:	
	Pond 1: $684 \text{ ft} < h \le 684.5 \text{ ft}$ Pond 2A/2B: $682.7 \text{ ft} < h \le 683.2 \text{ ft}$ Pond 3: $679.4 \text{ ft} < h \le 679.9 \text{ ft}$	
	For an Event Level 2 to be declared as a result of flooding, no water would be overtopping the perimeter dikes, and the pond water surface elevation would be as follows:	2
	Pond 1: $684.5 \text{ ft} < h \le 687.5 \text{ ft}$ Pond $2A/2B$ : $683.2 \text{ ft} < h \le 685.5 \text{ ft}$	
	Pond 3: $679.9 \text{ ft} < h \le 684.5 \text{ ft}$	



### TABLE 1.1 - EVENT LEVEL DETERMINATION GUIDANCE

	.1 - EVENT LEVEL DETERMINATION GUIDANCE	Event
Event	Observation	Level
Flooding and Overtopping	For an Event Level 1 to be declared as a result of flooding, some	1
	waves may be observed to be flowing over the tops of the perimeter	
	dikes, and the pond water surface elevation would be as follows:	
	Pond 1: $h > 687.5$ ft	
	Pond 2A/2B: $h > 685.5$ ft	
	Pond 3: $h > 684.5$ ft	
Earthquake and	This minimum event level will be declared any time an earthquake	3
Aftershocks	occurs within 50 miles of the station regardless of the earthquake magnitude. A field inspection of the Ash Pond System dikes shall immediately commence to determine if an Event Level 2 or 1 is warranted.	
	This is the minimum event level to be declared in the event that the post-earthquake inspections of the Ash Pond System indicate damage has occurred to the ash pond perimeter dikes, but there is no indication of fluids escaping from the ponds. Observed damage may include, but not be limited to, sloughing, vertical or horizontal cracks, and/or bulging.	2
	This event level will be declared in the event that the post-earthquake inspections indicate that there are some fluids escaping from the pond through the Ash Pond System perimeter dikes.	1
Seepage and Erosion	This event level should be declared upon discovery of seepage; or, in other words, a slow escape of liquid through the earthen material of any ash pond dike. The discovery of seepage may also coincide with the discovery of surface scouring and erosion. For an Event Level 3, the seepage should be clear and clean of suspended solids and of a relatively low flow rate. This event level may also be declared upon observation of spongy feeling, soft, wet soils located near the downstream toe of a dike.	3
	This event level should be declared when a significant increase in the seepage flow rate is observed or a discoloration of the flow is observed. This event level should also be declared if minor erosion is observed on the surface of the dike. Erosion can be defined as the scouring of the surface of the dike such that soil material has visibly been removed from the dike surface.	2
	This event level should be declared upon discovery of seepage flow that contains visible evidence of solids or any other indication that significant internal or external erosion is occurring. Such external erosion may be evident by the presence of a significant flow path or erosion channel on the surface of the dike.	_11
Cracking and other Movements	This event level should be declared upon discovery of a new crack greater than ½" but less than 1" in width or observation of movement of the dike which may include sloughing or bulging.	3
	This event level should be declared upon observation of significantly increased cracking (cracks greater than 1" in width) or increased movement areas, but there is no evidence of seepage flow from the pond.	2



### TABLE 1.1 - EVENT LEVEL DETERMINATION GUIDANCE

T. 4		Event Level
Event	Observation	
Cracking and other	This event level should be declared upon observation of significantly	
Movements	increased cracking (cracks greater than 1" in width) or increased	
	movement areas and there is evidence of seepage flow from the pond,	
	such as the sloughed area is moist or water is visibly flowing out of	
Discharge Discharge Value	the dike.	3
Discharge Piping Valve	This event level should be declared upon discovery of a blocked	3
Failure or Blocked	discharge pipe or a malfunctioning discharge valve. This event level should be declared even if the valve cannot be closed.	
Discharge Pipes	This event level should be declared upon discovery of a blocked	2
	discharge pipe or a malfunctioning discharge valve and the pond water	2
	surface elevation, h, is as follows:	
	Pond 1: $684.5 \text{ ft} < h \le 687.5 \text{ ft}$	
	Pond 2A/2B: $683.2 \text{ ft} < h \le 685.5 \text{ ft}$	
	Pond 3: $679.9 \text{ ft} < h \le 684.5 \text{ ft}$	1
	This event level should be declared upon discovery of a blocked discharge pipe or a malfunctioning discharge valve and the pond water	1
	surface elevation, h, is as follows:	
	Pond 1: $h > 687.5$ ft	
	Pond 2A/2B: $h > 685.5$ ft	
	Pond 3: $h > 684.5$ ft	
Sabotage	This event level should be declared if Sabotage is ever suspected to	3
	have occurred at any location within the Harding Street Generating	
	Station and there is no visible evidence of leakage from the Ash Pond	
	System dikes.	
	This event level should be declared if Sabotage is ever determined to	2
	have occurred at any location within the Harding Street Generating	
	Station and there is no visible evidence of leakage from the Ash Pond	
	System dikes.	1
	This event level should be declared if Sabotage is ever determined to	1
	have occurred at any location within the Harding Street Generating	
	Station and there is visible evidence of leakage from the Ash Pond	
	System dikes.	

### TABLE 1.2 – POND DIKE ELEVATIONS AND MAXIMUM SURFACE WATER ELEVATIONS

	Existing Minimum Dike Crest Elevation <sup>1</sup>	Maximum Design Water Surface Elevation <sup>1</sup>
Pond Name	(feet)	(feet)
Pond 1	688	684
Pond 2A/2B	686	682.7
Pond 3	685	679.4

<sup>&</sup>lt;sup>1</sup> Elevations are with respect to the North American Vertical Datum of 1988 (NAVD88).



## SECTION 2. NOTIFICATION AND COMMUNICATION

This section of the EAP describes the appropriate notifications that should be made after the EAP Coordinator has determined the event level as an Event Level 3, 2, or 1. This section also outlines the communication systems that are available for making notifications as well as a Public Affairs Plan with a sample media release and a list of media contacts. Notifications should be made in accordance with the appropriate Notification Flow Chart provided in this Section (Figures 2.1, 2.2, and 2.3).

### 2.1 COMMUNICATION SYSTEMS

Every effort will be made to communicate the occurrence of an incident or event to the EAP Coordinator as soon as possible. Communication regarding the event details will be made by plant personnel observing the situation using systems most available at the time that the event is observed. Methods of communication available include, in order of preference; cell phones, radios, GAI-Tronics, pagers, or e-mails. The EAP Coordinator should then contact all other interested parties in accordance with the appropriate Notification Flow Chart by telephone.

### 2.2 SUGGESTED PRESCRIPTED MESSAGES FOR EAP COORDINATOR

The following prescripted messages may be used as a guide to communicate the status of an event. Keep in mind that clarity and brevity are the most important qualities of these messages.

### **Event Level 3**

- This is the Emergency Action Plan Coordinator. I am making this call in accordance with the Harding Street Ash Pond System EAP.
- An incident has been detected at the Ash Pond System.
- The EAP has been activated, currently at an incident level (Level 3).
- If a problem occurs, flooding along the White River, in and around Harding Street Generating Station, and along Lick Creek is possible.
- The situation is being monitored to determine if any evacuation warnings are necessary.
- We will keep you apprised of the situation. The best telephone number to reach me during this event is ... (state the best number to reach you).

### **Event Level 2**

- This is the Emergency Action Plan Coordinator. I am making this call in accordance with the Harding Street Ash Pond System EAP.
- Problems have occurred with the Ash Pond System.
- The EAP has been activated, currently at the emergency level (Level 2).
- Flooding along the White River, in and around the Harding Street Generating Station, and along Lick Creek is possible.
- Prepare to limit access to areas (1) along the White River between S Harding Street Bridge and the Interstate 465 Bridge, and (2) to station areas near the ash pond dikes and Lick Creek.
- We will keep you apprised of the situation. The best telephone number to reach me during this event is ... (state the best number to reach you).



### **Event Level 1**

- This is the Emergency Action Plan Coordinator. I am making this call in accordance with the Harding Street Ash Pond System EAP.
- Problems have occurred with the Ash Pond System.
- The EAP has been activated, currently at the highest emergency level (Level 1).
- Flooding on station property near Lick Creek and along the White River will occur.
- Immediately establish restricted access areas along the White River between the S Harding Street Bridge upstream of the station and the Interstate 465 Bridge downstream of the station.
- Immediately instruct plant personnel to move to higher ground away from the Ash Pond System and Lick Creek.
- We will keep you apprised of the situation. The best telephone number to reach me during this event is ... (state the best number to reach you).

### 2.3 PUBLIC AFFAIRS PLAN

In the event of an incident or an emergency condition, the Public Relations Director will be alerted and briefed on the situation. The Public Relations Director will prepare and deliver a message for public release based on the existing conditions and information from the Engineering Director or designee, or other sources.

Preparation of warning messages should begin as soon as their potential need is apparent so that they can be issued promptly upon determination of a Level 2 or Level 1 event. Where time is available for its preparation, the initial message should contain all pertinent information. However, in some cases, an emergency condition may be declared with little or no advance notice. The following example messages provide a model for the first announcements in such cases for Event Levels 2 and 1. Subsequent announcements should provide additional details.

### **Announcement for Possible Dike Failure Problem (Event Level 2)**

The Indianapolis Power & Light Company announced at (time) today that an emergency condition existed around the Harding Street Generating Station Ash Pond System dikes due to (general description of problem). The Ash Pond System is located 2.0 miles upstream from the Interstate 465 Bridge over the White River, southwest of Indianapolis, Indiana.

The IPL spokesperson said that actions were underway to prevent failure of the Ash Pond System dikes and there is no immediate danger of the dikes failing. However, as a precautionary measure, those located on or along the banks of the White River downstream of the S Harding Street Bridge and upstream of the Interstate 465 Bridge should prepare to evacuate.

Additional information will be released as promptly as possible.





### **Announcement for Possible Dike Failure Imminent or in Progress (Event Level 1)**

**URGENT, URGENT:** The Indianapolis Power & Light Company announced at (time) today that an emergency condition existed around the Harding Street Generating Station Ash Pond System due to (general description of problem). The Ash Pond System is located 2.0 miles upstream from the Interstate 465 Bridge over the White River, southwest of Indianapolis, Indiana.

Attempts to save the dikes are underway but their success cannot be determined as of yet. Anyone located on or along the banks of the White River downstream of the S Harding Street Bridge and upstream of the Interstate 465 Bridge should evacuate to higher ground **IMMEDIATELY!** 


If the dike fails, water will take less than 30 minutes for the flood wave to travel from the dike breach to the Interstate 465 Bridge. Areas closer to the station will be flooded sooner.


Additional information will be released as promptly as possible.


### **Media Contacts**

The National Weather Service shall be the primary source through which emergency announcements are released to the news media. Several other radio and television stations that are likely to provide coverage to the area in danger are also included below in the case that the primary source cannot be reached.

Primary Source	
NATIONAL WEATHER SERVICE (24-hour telephone number):	(317)-856-0367
	, ,
<b>Secondary Sources</b> (Shall be contacted only if the primary source cannot be reached.)	
Television Stations	
WTHR (ATSC CHANNEL 13.1) (24-hour telephone number):	(317)-636-1313
WISH (ATSC CHANNEL 8.1) (24-hour telephone number):	(317)-923-8888
WRTV (ATSC CHANNEL 6.1) (24-hour telephone number):	(317)-248-6379
WXIN-WTTV (ATSC CHANNEL 49.1-4.1/29.1):	(317)-632-5900
Radio Stations	
WCBK 102.3 FM (24-hour telephone number):	(317)-831-3394
WTTS 92.3 FM (24-hour telephone number):	(800)-923-9887
WFBQ 94.7 FM (24-hour telephone number):	
WFMS 95.5 FM (24-hour telephone number):	(317)-842-9550









## SECTION 3. EXPECTED ACTIONS

### 3.1 ACTION DATA SHEETS

After the EAP Coordinator (or Acting EAP Coordinator) has determined the event level and has made the appropriate notifications, the EAP Coordinator shall take action, using the general procedure outlined in the Action Data Sheets that follow as a guide. Table 3.1 is an index of the Action Data Sheets.

The Action Data Sheets should be reviewed by the Engineering Director (or designee) and/or the On-Call Engineer when possible and time permits. If an event is not adequately covered by one of the general procedures outlined in the following procedures, adapt an Action Data Sheet of a similar event and event level specific to the event that requires additional or varied actions.

TABLE 3.1 – ACTION DATA SHEET INDEX

Event	<b>Event Level</b>	Action Data Sheet
	3	A3
Flooding and Overtopping	2	A2
	1	A1
	3	В3
Earthquake	2	B2
	1	B1
	3	C3
Seepage and Erosion	2	C2
	1	C1
Cracking and other Movements	3	D3
	2	D2
Movements	1	D1
Discharge Piping Valve	3	E3
Failure or Blocked	2	E2
Discharge Pipes	1	E1
	3	F3
Sabotage	2	F2
	1	F1



Time/Date

Completed

EVENT: Flooding and Overtopping LEVEL: 3	Action Data Sheet: A3
RECOMMENDED ACTIONS	

### **EAP Coordinator:**

- A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.
- B. Monitor the installed staff gauges to determine if the surface water level within the pond is rising or falling and at what rate. Additionally, a careful inspection of the perimeter dike and inlet/outlet piping for the pond which is at risk of overtopping shall be performed to determine if there are any other signs of degradation, erosion, or structural instability. This should be done without compromising the safety of anyone performing the inspection.
- C. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.
- D. Record all information, observations, and actions on an Event Log Form (Form 3.1).
- E. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.

### **Engineering Director or designee:**

A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.

### **On-Call Engineer:**

A. Provide decision support and technical support to the Engineering Director or designee as appropriate.

### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event can be terminated. The event may be terminated when the pond water surface elevation drops below the maximum surface water elevation for that particular pond.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 3 while the pond water surface elevation, h, is as follows:

Pond 1: 684 ft < h ≤ 684.5 ft</li>
 Pond 2A/2B: 682.7 ft < h ≤ 683.2 ft</li>
 Pond 3: 679.4 ft < h < 679.9 ft</li>

C. The event warrants escalation to Event Level 2. The Event Level shall be raised to Event Level 2 if the pond water surface elevation, *h*, is as follows:

Pond 1: h > 684.5 ft
 Pond 2A/2B: h > 683.2 ft
 Pond 3: h > 679.9 ft

A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEVEL 2
Go to Termination and Follow-up	Continue recommended actions	Go to <b>Event Level 2</b> or <b>Event Level 1</b>
(Section 4)	on this sheet	Notification Chart



Time/Date

Completed

EVENT: Flooding and Overtopping LEVEL: 2 Action Data Sheet: A2

### RECOMMENDED ACTIONS

### **EAP Coordinator:**

- A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.
- B. Monitor the installed staff gauges to determine if the water surface level within the pond is rising or falling and at what rate. Continue to perform careful inspections of the perimeter dike and inlet/outlet piping for the subject pond at risk of overtopping on a frequent basis to determine if there are any other signs of degradation, erosion, or structural instability. This should be done without compromising the safety of anyone performing the inspection.
- C. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.
- D. Record all information, observations, and actions on an Event Log Form (Form 3.1).
- E. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.

### **Engineering Director or designee:**

A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.

### **On-Call Engineer:**

A. Provide decision support and technical support to the Engineering Director or designee as appropriate.

### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

A. The event warrants downgrade to Event Level 3. All contacts on Event Level 2 Notification Flow Chart shall be notified of downgrade from Event Level 2 to Event Level 3. The event level may be downgraded if the pond water surface elevation, *h*, is as follows:

Pond 1: h ≤ 684.5 ft
 Pond 2A/2B: h ≤ 683.2 ft
 Pond 3: h ≤ 679.9 ft

B. The event remains at the current Event Level. The event level shall remain at Event Level 2 while the pond water surface elevation, h, is as follows:

Pond 1: 684.5 ft < h ≤ 687.5 ft</li>
 Pond 2A/2B: 683.2 ft < h ≤ 685.5 ft</li>
 Pond 3: 679.9 ft < h ≤ 684.5 ft</li>

C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 when the pond water surface elevation, h, is as follows:

Pond 1: h > 687.5 ft
 Pond 2A/2B: h > 685.5 ft
 Pond 3: h > 684.5 ft

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart



EVENT LEVEI	T: Flooding and Overtopping	Action Data Sheet: A1		
	RECO	MMENDED ACTIONS		
EAP C	oordinator:		Time/Date	
A.	Make sure notifications to all partie	es are completed in accordance with the outline	Completed	
	included in Section 2.2.			
B.		aff gauges to determine if the water surface level		
	within the pond is rising or falling and			
C.		tor or designee and/or the On-Call Engineer to		
_	determine any corrective/preventative			
D.		ze the potential for human loss of life, injury, or		
	property damage should the dikes over			
		and actions on an Event Log Form (Form 3.1).		
F.		contact with the Engineering Director or designee		
	until Event Level 1 is terminated.			
Engine	ering Director or designee:			
		rder to recommend appropriate actions to the EAP		
11.		by contractors and/or other individuals that may be		
	able to assist in monitoring or repairing			
	dote to assist in monitoring of repairing the steamen.			
On-Cal	l Engineer:			
A.	Provide decision support and technical	I support to the Engineering Director or designee as		
	appropriate. Send a qualified individua	al to the site as soon as possible.		
1				

### **EVALUATION / DECISION**

Evaluate conditions at least twice daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

A. The event warrants downgrade to Event Level 2. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level 2. The event level may be downgraded if the pond water surface elevation, *h*, is as follows:


Pond 1: h ≤ 687.5 ft
 Pond 2A/2B: h ≤ 685.5 ft
 Pond 3: h ≤ 684.5 ft

B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as the pond water surface elevation, h, is as follows:

Pond 1: h > 687.5 ft
 Pond 2A/2B: h > 685.5 ft
 Pond 3: h > 684.5 ft

C. The event can be terminated after a failure event occurs and the pond completely drains to a point where there is no further threat to human loss of life, injury, or property damage.

A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINATED
Go to Event Level 2 Notification	Continue recommended actions	Go to Termination and Follow-Up
Chart	on this sheet	(Section 4)





NOT TO SCALE



NOTES 1. AFRIAL IMAGE. DATED 10-17-20'5. SHOWN ON THIS DRAWING WAS OBTAINED USING GOOGLE EARTH PRO v6.2.

HOLD INFORMATION DESCRIPTION

RELEASE INFORMATION

DESCRIPTION

REV. DATE 0 03-23-2017 FOR USE

ISSUE PURPOSE: USE SPECIFICATION:

PREPARED BY: JF REVIEWED BY: DK APPROVED BY: DN

PROJECT NO.: 10572-088

CAD FILE NAME: HS EAP - FIGURE 5.2.DGN

ANY MODIFICATION OR ADDITION TO THIS DRAWING BY AN ORGANIZATION OTHER THAN SARGENT & LUNDY IS NOT THE RESPONSIBILITY OF SARGENT & LUNDY.

Sargent & Lundy"

SARGENT & LUN)Y\*\*\*
55 EAST MONROE STREET
CHICAGO: ILLINDIS (0603-5780

HARDING STREET GENERATING STATION EMERGENCY ACTION PLAN

DRAWING TITLE ASH POND SYSTEM LAYOUT ANNOTATED AERIAL PHOTOGRAPH

> DRAWING NUMBER FIGURE 5.2 0

NOT TO SCALE



NOTES AERIAL IMAGE, DATED 10-17-20'5, SHOWN ON THIS DRAWING WAS OBTAINED USING GODGLE EARTH PRO v6.2.

HOLD INFORMATION DESCRIPTION

> RELEASE INFORMATION REV. DATE 0 03-23-2017 FOR USE DESCRIPTION

ISSUE PURPOSE: USE

SPECIFICATION: PROJECT NO.: 10572-088

CAD FILE NAME: HS EAP - FIGURE 5.3.DGN

PREPARED BY: JF

REVIEWED BY: DK APPROVED BY: DN

ANY MODIFICATION OR ADDITION TO THIS DRAWING BY AN ORGANIZATION OTHER THAN SARGENT & LUNDY IS NOT THE RESPONSIBILITY OF SARGENT & LUNDY.

Sargent & Lundy

SARGENT & LUNDY "
55 EAST MONROE STREET
CHICAGO. ILLINOIS (0603-5780




PROJECT

HARDING STREET GENERATING STATION EMERGENCY ACTION PLAN

DRAWING TITLE EMERGENCY SITE ACCESS

ROUTE MAP

DRAWING NUMBER REVISION FIGURE 5.3 0



1" = 400'-0"

RELEASE INFORMATION DESCRIPTION 0 03-23-2017 FOR USE ISSUE PURPOSE: USE PROJECT NO.: 10572-088 CAD FILE NAME: FIGURE 5.4.DGN

HOLD INFORMATION

DESCRIPTION

Sargent & Lundy'''

SARGENT & LUNDY \*\*\*
55 EAST MONROE STREET
CHICAGO, ILLINDIS 60603-5780




HARDING STREET GENERATING STATION EMERGENCY ACTION PLAN


DRAWING TITLE


ESTIMATED DIKE BREACH INUNDATION MAP

DRAWING NUMBER REVISION FIGURE 5.4 0

ZD11104/011144/S:#|PL#Topo Exhibits#Hording Street#Figure 5.4.1. Form GDG-0401-01-08. ANS| Imperial) MicroStation Border - Size Revision 11A. Revision Date: 04-30-2010







RELEASE INFORMATION

REV. DATE DESCRIPTION

O 03-23-2017 FOR USE

ISSUE PURPOSE: USE

ENCEITICATION

PROJECT NO.: 10572-088

HOLD INFORMATION
DESCRIPTION

SARGENT & LUNDY SE EXCLUSION SHEET SEARCH SE

CAD FILE NAME: HS EAP - FIGURE 5.5.DGN

PREPARED BY: JF

REVIEWED BY: DK

APPROVED BY: DN



PROJECT

HARDING STREET GENERATING STATION EMERGENCY ACTION PLAN

DRAWING TITLE

ASH POND SYSTEM

AREA AND CAPACITY CURVES

SHEET

FIGURE 5.5 O

NOTES

1. ALL ELEVATIONS ARE WITH RESPECT TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAV088).



EVENT: Earthqua LEVEL: 3	ake and Aftershocks	Action Data Sheet: B3	
	RECO	MMENDED ACTIONS	
EAP Coordinator:			Time/Date
	e notifications to all partie Section 2.2.	es are completed in accordance with the outline	Completed
B. Immediate inlet/outlet damage, d	ly commence a careful in piping for the entire Ash I	spection of all perimeter and interior dikes and Pond System to determine if there are any signs of ability. This should be done without compromising spection.	
•	, ,	and actions on an Event Log Form (Form 3.1).	
D. Repeat the inspection at least once per day for three days or until the Event Level has been raised to a Level 2.			
E. At the co		d inspection, contact the Engineering Director or ons and conditions.	
Engineering Director or designee:			
	ed to receive and respond to t	the field inspection report.	
On-Call Engineer: A. N/A.			
		TIATION / DECICION	

### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event can be terminated. The event may be terminated if there is no observable damage, degradation, or structural instability and more than three days have passed since the earthquake or once all observed damage, degradation, or structural instability has been addressed and/or repaired.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 3 if there is no observable damage, degradation, or structural instability and less than three days have passed since the earthquake.
- C. The event warrants escalation to Event Level 2. The Event Level shall be raised to Event Level 2 if a field inspection following the earthquake indicates that damage has occurred to the Ash Pond perimeter dikes, but there is no indication of fluids escaping from the ponds. Observed damage may include, but not be limited to, sloughing, vertical or horizontal cracks, and/or bulging.

A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEVEL 2
Go to Termination and Follow-up	Continue recommended actions	Go to Event Level 2 or Event Level 1
(Section 4)	on this sheet	Notification Chart



EVENT: Earthquake and Aftershocks LEVEL: 2  Action Data Sheet: B2					
		MMENDED ACTIONS			
EAP C	oordinator:		Time/Date		
		es are completed in accordance with the outline	Completed		
	B. Continue to monitor the damaged dike of the Ash Pond System and notify the Engineering Director or designee if any significant changes are observed. This should be done without compromising the safety of anyone performing the inspection.				
C.	Confer with the Engineering Direct determine any corrective/preventative	or or designee and/or the On-Call Engineer to			
D		and actions on an Event Log Form (Form 3.1).			
E.		esignee at least daily to report the latest observations			
Engine	ering Director or designee:				
A.		rder to recommend appropriate actions to the EAP			
	Coordinator. If necessary, contact lo that may be able to assist in monitoring	cal emergency contractors and/or other individuals g or repairing the situation.			
On-Cal	l Engineer:				
	B. Provide decision support and technical support to the Engineering Director or designee as appropriate.				
	EVAI				
Evaluat		conditions change significantly. Using Table 1.1 and	or Table 3.1		
	ne whether:	conditions change argumentary. Coming Tuest 111 untar	01 14010 5.1,		
		nt Level 3. The event level may be downgraded once	the observed		
	damage, degradation, or structural instability has been addressed and/or repaired. All contacts on Event Level 2 Notification Flow Chart shall be notified of downgrade from Event Level 2 to Event Level 3.				
B.		nt Level. The event level shall remain at Event Level tural instability has been addressed and/or repaired.	el 2 until the		
C.		t Level 1. The Event Level shall be raised to Event I	evel 1 when		
	it is observed that there are some fluids escaping from the ponds through the Ash Pond System perimeter				

Based on this information, follow the appropriate actions below.

dikes.

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart



EVENT LEVEI	Γ: Earthquake and Aftershocks	Action Data Sheet: B1	
DEVE		OMMENDED ACTIONS	
EAP C	oordinator:		Time/Date
		es are completed in accordance with the outline	Completed
	Director or designee if any significant compromising the safety of anyone per		
C.	Confer with the Engineering Direct determine any corrective/preventative	tor or designee and/or the On-Call Engineer to actions that must be taken.	
D.	Take all necessary actions to minimi property damage should the dikes fail.	ize the potential for human loss of life, injury, or	
E.		and actions on an Event Log Form (Form 3.1).	
F.		t contact with the Engineering Director or designee	
Engine	ering Director or designee:		
A.		rder to recommend appropriate actions to the EAP cal emergency contractors and/or other individuals g or repairing the situation.	
On-Cal	ll Engineer:		
A.	Provide decision support and technica appropriate. Send a qualified individu	l support to the Engineering Director or designee as al to the site as soon as possible.	
	EVAl	LUATION / DECISION	
determi	ne whether:	conditions change significantly. Using Table 1.1 and	
A.		ent Level 2. The event level may be downgraded onc	

- fluids escaping from the ponds through the Ash Pond System perimeter dikes ceases. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level
  - 2.B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as fluids are escaping from the ponds through the Ash Pond System perimeter dikes.
  - C. The event can be terminated after a failure event occurs and the pond completely drains to a point where there is no further threat to human loss of life, injury, or property damage.

A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINATED
Go to Event Level 2 Notification	Continue recommended actions	Go to Termination and Follow-Up
Chart	on this sheet	(Section 4)



EVENT LEVEL	Seepage and Erosion Action Data Sheet: C3			
	RECOMMENDED ACTIONS			
EAP Co	oordinator:	Time/Date		
A.	Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.	Completed		
В.	B. A careful inspection of the perimeter dike and inlet/outlet piping for the dike which has observed seepage and erosion shall be performed to determine if there are any other signs of degradation, erosion, or structural instability. This should be done without compromising the safety of anyone performing the inspection. If necessary, confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.			
C.	Record all information, observations, and actions on an Event Log Form (Form 3.1).			
D.	D. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.			
Engine	ering Director or designee:			
	Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.			
On-Cal	Engineer:			
	Provide decision support and technical support to the Engineering Director or designee as appropriate.			
	EVALUATION / DECISION			
Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1,				
	ne whether:	ŕ		
A.	A. The event can be terminated. The event may be terminated once the perimeter dike has been repaired and the observed seepage of fluids has ceased.			
В.	The event remains at the current Event Level. The event level shall remain at Event Level seepage continues and the fluids are clear, clean of suspended solids and of a relatively low in			

Based on this information, follow the appropriate actions below.

	A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEVEL 2
	Go to Termination and Follow-up	Continue recommended actions	Go to Event Level 2 or Event Level 1
	(Section 4)	on this sheet	Notification Chart

Event Level shall also be raised if minor erosion of the dike surface is observed.

C. The event warrants escalation to Event Level 2. The Event Level shall be raised to Event Level 2 if a significant increase in the seepage flow rate is observed or a discoloration of the flow is observed. The



EVENT: Seepage and Erosion Action Data Sheet: C2				
LEVEL: 2 Action Data Sheet. C2				
RECOMMENDED ACTIONS				
EAP Coordinator:	Time/Date			
	Completed			
included in Section 2.2.				
B. Continue to monitor the perimeter dike where the seepage and/or erosion have been				
observed on a daily basis and notify the Engineering Director or designee if any				
significant changes are observed. This should be done without compromising the safety of anyone performing the inspection.				
C. Confer with the Engineering Director or designee and/or the On-Call Engineer to				
determine any corrective/preventative actions that must be taken.				
D. Record all information, observations, and actions on an Event Log Form (Form 3.1).				
E. Contact the Engineering Director or designee at least daily to report the latest observations				
and conditions.				
Engineering Director or designee:				
A. Review all pertinent information in order to recommend appropriate actions to the EAP				
Coordinator. If necessary, contact local emergency contractors and/or other individuals				
that may be able to assist in monitoring or repairing the situation.				
On-Call Engineer:				
A. Provide decision support and technical support to the Engineering Director or designee as				
appropriate.				
EVALUATION / DECISION				

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event warrants downgrade to Event Level 3. The event level may be downgraded when the observed rate of seepage decreases to a relatively low rate and the color of the seepage becomes clear, indicative of significantly less suspended solids. All contacts on Event Level 2 Notification Flow Chart shall be notified of downgrade from Event Level 2 to Event Level 3.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 2 until the rate of seepage decreases to a relatively low rate and the color of the seepage becomes clear, indicative of significantly less suspended solids.
- C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 upon discovery of seepage flow that contains visible evidence of solids or any other indication that significant internal or external erosion is occurring. Such external erosion may be evident by the presence of a significant flow path or erosion channel on the surface of the dike.

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart



EVENT: Seepage and Erosion					
LEVEL: 1	Action Data Sheet: C1				
RECOMMENDED ACTIONS					
EAP Coordinator:		Time/Date			
A. Make sure notifications to all participation included in Section 2.2.	es are completed in accordance with the outline	Completed			
	B. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.				
C. Take all necessary actions to minimize the potential for human loss of life, injury, or property damage should the dike fail.					
	D. Record all information, observations, and actions on an Event Log Form (Form 3.1).				
E. Establish a means to keep in frequent contact with the Engineering Director or designee until Event Level 1 is terminated.					
Engineering Director or designee:					
A. Review all pertinent information in o	rder to recommend appropriate actions to the EAP cal emergency contractors and/or other individuals g or repairing the situation.				
On-Call Engineer:					
	I support to the Engineering Director or Designee as al to the site as soon as possible.				
EVALUATION / DECISION					
Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1,					
determine whether:					
A. The event warrants downgrade to Event Level 2. The event level may be downgraded once fluids cease					

- - escaping from the ponds through the Ash Pond System perimeter dikes. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level 2.
  - B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as fluids are escaping from the ponds through the Ash Pond System perimeter dikes.
  - C. The event can be terminated after a failure event occurs and the pond completely drains to a point where there is no further threat to human loss of life, injury, or property damage.

A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINATED
Go to Event Level 2 Notification	Continue recommended actions	Go to Termination and Follow-Up
Chart	on this sheet	(Section 4)

(Section 4)



Report No. SL-013824 Project No. 10572-088 Rev. 0 March 31, 2017

EVENT: Cracking and Other Movements LEVEL: 3  Action Data Sheet: D3				
RECOMMENDED ACTIONS				
EAP Coordinator:	110 011111201 12 02 12 0 12 0 1		Time/Date	
	all parties are completed in acc	cordance with the outline	Completed	
B. A careful and complete inspection of the entire pond shall be performed to determine if there are any other signs of degradation, erosion, or structural instability beyond those already observed. This should be done without compromising the safety of anyone performing the inspection.				
	ng Director or designee and/or ventative actions that must be taken			
<ul> <li>D. Record all information, observations, and actions on an Event Log Form (Form 3.1).</li> <li>E. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.</li> </ul>				
Engineering Director or designee:  A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.  On-Call Engineer:  A. Provide decision support and technical support to the Engineering Director or designee as				
appropriate.				
	EVALUATION / DECISION			
Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1 determine whether:  A. The event can be terminated. The event may be terminated once the observed cracks or dike movements				
have been repaired.				
B. The event remains at the current Event Level. The event level shall remain at Event Level 3 until the observed cracks and/or dike movements are repaired.				
C. The event warrants escalation to Event Level 2. The Event Level shall be raised to Event Level 2 if a significant increase in cracking (cracks greater than 1" in width) or increased movement areas are observed but there is no evidence of seepage flow through the pond perimeter dike.				
Based on this information, follow the appropriate actions below.				
A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEV	EL 2	
Go to Termination and Follow-up	Continue recommended actions	Go to <b>Event Level 2</b> or <b>E</b>	vent Level 1	

on this sheet

**Notification Chart** 



EVENT LEVEL	: Cracking and Other Movements : 2  Action Data Sheet: D2		
DEVEL	RECOMMENDED ACTIONS		
EAP Co	ordinator:	Time/Date	
A.	Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.	Completed	
	Continue to monitor the perimeter dike on a daily basis where the cracks or movements have been observed and notify the Engineering Director or designee if any significant changes are observed. This should be done without compromising the safety of anyone performing the inspection.		
C.	Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.		
D. E.	Record all information, observations, and actions on an Event Log Form (Form 3.1).		
Enginee A.	Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.		
	Engineer: Provide decision support and technical support to the Engineering Director or designee as appropriate.		
	EVALUATION / DECISION		
	e conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and the whether:	or Table 3.1,	
	The event warrants downgrade to Event Level 3. The event level may be downgraded when cracks or dike movements are repaired. All contacts on Event Level 2 Notification Flow Contified of downgrade from Event Level 2 to Event Level 3.	Chart shall be	
B. The event remains at the current Event Level. The event level shall remain at Event Level 2 until the observed cracks or dike movements are repaired.			
C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 upon discovery of seepage flow through the pond perimeter dike. This may include the observation of visually evident flowing water or that the sloughed area is moist.			
Based o	n this information, follow the appropriate actions below.		

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart



	C: Cracking and Other Movements Action Data Sheet: D1				
LEVEL	LEVEL: I				
EADC	RECOMMENDED ACTIONS	Time/Date			
	Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.	Completed			
В.	Continue to monitor the perimeter dike where the cracks, seepage and/or erosion have been observed and notify the Engineering Director or designee if any significant changes are observed. This should be done without compromising the safety of anyone performing the inspection.				
C.	Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.				
D.	Take all necessary actions to minimize the potential for human loss of life, injury, or property damage should the dike fail.				
	± ± 7 × 9				
Engine	ering Director or designee:				
	A. Review all pertinent information in order to recommend appropriate actions to the EAP coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.				
On-Cal	l Engineer:				
	Provide decision support and technical support to the Engineering Director or designee as appropriate. Send a qualified individual to the site as soon as possible.				
	EVALUATION / DECISION				
	e conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and ne whether:	or Table 3.1,			
A.	A. The event warrants downgrade to Event Level 2. The event level may be downgraded once the flow of fluids escaping from the ponds through the Ash Pond System perimeter dikes ceases. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level 2.				
	<ul> <li>B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as fluids are escaping from the ponds through the Ash Pond System perimeter dikes.</li> <li>C. The event can be terminated after a failure event occurs and the pond completely drains to a point where there is no further threat to human loss of life, injury, or property damage.</li> </ul>				

A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINATED
Go to Event Level 2 Notification	Continue recommended actions	Go to Termination and Follow-Up
Chart	on this sheet	(Section 4)



Time/Date

Completed

EVENT: Discharge Piping Valve Failure or Blocked Discharge Pipes LEVEL: 3	Action Data Sheet: E3
---	-----------------------

#### RECOMMENDED ACTIONS

#### **EAP Coordinator:**

A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.

- B. Monitor the installed staff gauges to determine if the surface water level within the pond is rising or falling and at what rate. Additionally, a careful inspection of the perimeter dike and inlet/outlet piping for the pond which is at risk of overtopping shall be performed to determine if there are any other signs of degradation, erosion, or structural instability. This should be done without compromising the safety of anyone performing the inspection.
- C. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.
- D. Record all information, observations, and actions on an Event Log Form (Form 3.1).
- E. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.

#### **Engineering Director or designee:**

A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.

#### **On-Call Engineer:**

A. Provide decision support and technical support to the Engineering Director or designee as appropriate.

#### EVALUATION / DECISION

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event can be terminated. The event may be terminated when the discharge piping valve is repaired or the blocked discharge pipes are cleared.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 3 while the discharge piping valve remains unrepaired or the blocked discharge pipes remain blocked.
- C. The event warrants escalation to Event Level 2. The Event Level shall be raised to Event Level 2 if the pond water surface elevation, *h*, is as follows:

Pond 1: h > 684.5 ft
 Pond 2A/2B: h > 683.2 ft
 Pond 3: h > 679.9 ft

A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEVEL 2
Go to Termination and Follow-up	Continue recommended actions	Go to <b>Event Level 2</b> or <b>Event Level 1</b>
(Section 4)	on this sheet	Notification Chart



Time/Date

Completed

EVENT: Discharge Piping Valve Failure or Blocked Discharge Pipes Action Data Sheet: E2

LEVEL: 2

#### RECOMMENDED ACTIONS

#### **EAP Coordinator:**

A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.

- B. Monitor the installed staff gauges to determine if the water surface level within the pond is rising or falling and at what rate. Perform regular inspections of all perimeter dikes and inlet/outlet piping for the subject pond at risk of overtopping to determine if there are any other signs of degradation, erosion, or structural instability. This should be done without compromising the safety of anyone performing the inspection.
- C. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.
- D. Record all information, observations, and actions on an Event Log Form (Form 3.1).
- E. Contact the Engineering Director or designee at least daily to report the latest observations and conditions. If conditions change significantly, contact the Engineering Director immediately.

#### **Engineering Director or designee:**

A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. If necessary, contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.

#### **On-Call Engineer:**

A. Provide decision support and technical support to the Engineering Director or designee as appropriate.

#### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

A. The event warrants downgrade to Event Level 3. All contacts on Event Level 2 Notification Flow Chart shall be notified of downgrade from Event Level 2 to Event Level 3. The event level may be downgraded if the pond water surface elevation, *h*, is as follows:

Pond 1: h ≤ 684.5 ft
 Pond 2A/2B: h ≤ 683.2 ft
 Pond 3: h ≤ 679.9 ft

B. The event remains at the current Event Level. The event level shall remain at Event Level 2 while the pond water surface elevation, h, is as follows:

• Pond 1:  $684.5 \text{ ft} < h \le 687.5 \text{ ft}$ • Pond 2A/2B:  $683.2 \text{ ft} < h \le 685.5 \text{ ft}$ • Pond 3:  $679.9 \text{ ft} < h \le 684.5 \text{ ft}$ 

C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 when the pond water surface elevation, h, is as follows:

Pond 1: h > 687.5 ft
 Pond 2A/2B: h > 685.5 ft
 Pond 3: h > 684.5 ft

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart



Time/Date

Completed

EVENT: Discharge Piping Valve Failure or Blocked Discharge Pipes LEVEL: 1  Action Data Sheet: E1
--

#### RECOMMENDED ACTIONS

#### **EAP** Coordinator:

- A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.
- B. Continue to monitor the installed staff gauges to determine if the water surface level within the pond is rising or falling and at what rate.
- C. Confer with the Engineering Director or designee and/or the On-Call Engineer to determine any corrective/preventative actions that must be taken.
- D. Take all necessary actions to minimize the potential for human loss of life, injury, or property damage should the dikes overtop, erode, and fail.
- E. Record all information, observations, and actions on an Event Log Form (Form 3.1).
- F. Establish a means to keep in frequent contact with the Engineering Director or designee until Event Level 1 is terminated.

#### **Engineering Director or designee:**

A. Review all pertinent information in order to recommend appropriate actions to the EAP Coordinator. Contact local emergency contractors and/or other individuals that may be able to assist in monitoring or repairing the situation.

#### **On-Call Engineer:**

A. Provide decision support and technical support to the Engineering Director or designee as appropriate. Send a qualified individual to the site as soon as possible.

#### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

A. The event warrants downgrade to Event Level 2. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level 2. The event level may be downgraded if the pond water surface elevation, h, is as follows:

Pond 1: h ≤ 687.5 ft
 Pond 2A/2B: h ≤ 685.5 ft
 Pond 3: h ≤ 684.5 ft

B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as the pond water surface elevation, h, is as follows:

Pond 1: h > 687.5 ft
 Pond 2A/2B: h > 685.5 ft
 Pond 3: h > 684.5 ft

C. The event can be terminated after a failure event occurs and the pond completely drains to a point where there is no further threat to human loss of life, injury, or property damage.

A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINATED
Go to Event Level 2 Notification	Continue recommended actions	Go to Termination and Follow-Up
Chart	on this sheet	(Section 4)



EVENT: Sabotage LEVEL: 3 Action Data Sheet: F3				
	RECO	DMMENDED ACTIONS		
<b>EAP Coordinator:</b>			Time/Date	
A. Make sure no included in Se	_	es are completed in accordance with the outline	Completed	
B. Immediately of inlet/outlet pip damage, degra	B. Immediately commence a careful inspection of all perimeter and interior dikes and inlet/outlet piping for the entire Ash Pond System to determine if there are any signs of damage, degradation, or structural instability. This should be done without compromising the safety of anyone performing the inspection.			
C. Record all info D. At the comple	C. Record all information, observations, and actions on an Event Log Form (Form 3.1).			
Engineering Director  A. Be prepared to		the field inspection report.		
On-Call Engineer: A. N/A.				
	EVALUATION / DECISION			

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event can be terminated. The event may be terminated if there is no observable damage, degradation, or structural instability, or once all observed damage, degradation, or structural instability is repaired.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 3 until any damage, degradation, or structural instability observed during the field investigation is appropriately repaired.
- C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 if the field inspection following the suspected Sabotage indicates that damage has occurred to the Ash Pond perimeter dikes and that there is visible evidence of fluid escaping through the pond perimeter dikes.

A) TERMINATION	B) EVENT LEVEL 3	C) EVENT LEVEL 1
Go to Termination and Follow-up	Continue recommended actions	Go to Event Level 1 Notification
(Section 4)	on this sheet	Chart



EAP Coordinator:  A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.  B. Immediately commence a careful inspection of all perimeter and interior dikes and inlet/outlet piping for the entire Ash Pond System to determine if there are any signs of damage, degradation, or structural instability. This should be done without compromising the safety of anyone performing the inspection.  C. Record all information, observations, and actions on an Event Log Form (Form 3.1).  D. At the completion of the field inspection, contact the Engineering Director or designee by telephone and report the observations and dike conditions.  Engineering Director or designee:  E. Be prepared to receive and respond to the field inspection report.  On-Call Engineer:  F. N/A.	EVENT: Sabotage LEVEL: 2	Action Data Sheet: F2	
A. Make sure notifications to all parties are completed in accordance with the outline included in Section 2.2.  B. Immediately commence a careful inspection of all perimeter and interior dikes and inlet/outlet piping for the entire Ash Pond System to determine if there are any signs of damage, degradation, or structural instability. This should be done without compromising the safety of anyone performing the inspection.  C. Record all information, observations, and actions on an Event Log Form (Form 3.1).  D. At the completion of the field inspection, contact the Engineering Director or designee by telephone and report the observations and dike conditions.  Engineering Director or designee:  E. Be prepared to receive and respond to the field inspection report.  On-Call Engineer:	RECO	MMENDED ACTIONS	
Engineering Director or designee:  E. Be prepared to receive and respond to the field inspection report.  On-Call Engineer:	EAP Coordinator:  A. Make sure notifications to all parties included in Section 2.2.  B. Immediately commence a careful ins inlet/outlet piping for the entire Ash Podamage, degradation, or structural instate the safety of anyone performing the insp.  C. Record all information, observations, and D. At the completion of the field inspection	s are completed in accordance with the outline spection of all perimeter and interior dikes and ond System to determine if there are any signs of ability. This should be done without compromising pection.  Indications on an Event Log Form (Form 3.1).  Indications on the Engineering Director or designee by	
	Engineering Director or designee:  E. Be prepared to receive and respond to the On-Call Engineer:		

#### **EVALUATION / DECISION**

Evaluate conditions at least daily, or whenever conditions change significantly. Using Table 1.1 and/or Table 3.1, determine whether:

- A. The event warrants downgrade to Event Level 3. The event level may be downgraded if there is no observable damage, degradation, or structural instability, or once all observed damage, degradation, or structural instability is repaired. All contacts on Event Level 2 Notification Flow Chart shall be notified of downgrade from Event Level 2 to Event Level 3.
- B. The event remains at the current Event Level. The event level shall remain at Event Level 2 until the observed damage, degradation or structural instability has been addressed and/or repaired.
- C. The event warrants escalation to Event Level 1. The Event Level shall be raised to Event Level 1 if the field inspection following the confirmed Sabotage indicates that damage has occurred to the Ash Pond perimeter dikes and that there is visible evidence of fluid escaping through the pond perimeter dikes.

A) EVENT LEVEL 3	B) EVENT LEVEL 2	C) EVENT LEVEL 1
Go to Event Level 3 Notification	Continue recommended actions	Go to Event Level 1 Notification
Chart	on this sheet	Chart

Chart



Report No. SL-013824 Project No. 10572-088 Rev. 0 March 31, 2017

EVENT: Sabotage	<b>Action Data She</b>	et: F1		
LEVEL: 1	RECOMMENDED ACTIONS			
EAP Coordinator:	RECOMMENDED ACTIONS	•	Time/Date	
	A. Make sure notifications to all parties are completed in accordance with the outline Completed			
Director or designee if any si compromising the safety of a	B. Continue to monitor the damaged dike of the Ash Pond System and notify the Engineering Director or designee if any significant changes are observed. This should be done without compromising the safety of anyone performing the inspection.			
	ng Director or designee and/or ventative actions that must be taken			
	o minimize the potential for hum			
	vations, and actions on an Event Le	og Form (Form 3.1).		
F. Establish a means to keep in frequent contact with the Engineering Director or designee until Event Level 1 is terminated.				
Engineering Director or designee:  A. Review all pertinent information in order to recommend appropriate actions to the EAP coordinator. If necessary, contact local emergency contractors and/or other individuals				
that may be able to assist in monitoring or repairing the situation.  On-Call Engineer:  A. Provide decision support and technical support to the Engineering Director or designee as appropriate. Send a qualified individual to the site as soon as possible.				
11 1	appropriate a quantitative and and an account possession			
EVALUATION / DECISION				
Evaluate conditions at least daily, or w determine whether:				
A. The event warrants downgrade to Event Level 2. The event level may be downgraded once the flow of fluids escaping from the ponds through the perimeter dike ceases. All contacts on Event Level 1 Notification Flow Chart shall be notified of downgrade from Event Level 1 to Event Level 2.				
B. The event remains at the current Event Level. The event level shall remain at Event Level 1 as long as fluids are escaping from the ponds through the perimeter dike.				
C. The event can be terminated after a failure event occurs and the pond completely drains to a point where				
there is no further threat to human loss of life, injury, or property damage.				
Based on this information, follow the appropriate actions below.				
A) EVENT LEVEL 2	B) EVENT LEVEL 1	C) TERMINAT	ΓED	
Go to Event Level 2 Notification	Continue recommended actions	Go to <b>Termination and</b>		

on this sheet

(Section 4)



# 3.2 LOCALLY AVAILABLE EQUIPMENT, LABOR, AND MATERIALS

The following is a list of the addresses and phone number(s) of nearby companies (e.g.; pump and other heavy equipment rental, crane service, etc.) that may be needed and are available and willing to provide services in the case of an emergency event. Since Ash Pond System emergencies may not just occur during business hours, these companies have a 24-hour contact number and they are specifically notified that they may be contacted at any time when an emergency is noted. All companies have agreed in writing to this condition and have provided a 24-hour contact number that is included in this EAP.

The contractors listed below have been retained by Harding Street Generating Station to provide the equipment, labor and materials deemed necessary to respond to emergency situations that may develop at the Ash Pond System of the Harding Street Generating Station.

SET Environmental	
Primary Contact:	Jennifer Holbrook
SET Environmental can provide the following services in the c	ease of an emergency event:
<ul> <li>Initial response,</li> </ul>	
• Excavation,	
<ul> <li>Remediation,</li> </ul>	
<ul> <li>Disposal, and</li> </ul>	
Hazardous Waste Operations and Emergency Response	e (HAZWOPER).
Denney Excavating	
Primary Contact:	Subcontractor for SET Environmental
Denney Excavating can provide the following services in the c	ase of an emergency event:
• Excavation,	
<ul> <li>Transportation, and</li> </ul>	
• HAZWOPER.	
Sub Surface of Indiana	
Primary Contact:	Todd Larson
3.3 INCIDENT OR EMERGENCY EVENT L	OG

Use the Incident or Emergency Event Log (Form 3.1) on the next page to record actions and events during an Incident or Emergency Event and the time that the action or event occurred.



# FORM 3.1 Incident or Emergency Event Log

# **Harding Street Generating Station – Ash Pond System**

You are	e (Circle		Designated Staff / On-Call Engineer / etor / or Warning/Evacuation Director
	What date	e and time did you detect/get notified of the you detect/get notified of the event?	e event? am/pm
,		ination al level has the EAP Coordinator (or designment) vent Progression	nee) assigned to the event?
Date	Time	Action/Event Progressio	n Taken By



# SECTION 4. TERMINATION AND FOLLOW-UP

Once EAP operations have begun under Event Level 3, 2, or 1, the EAP operations must eventually be terminated and follow-up procedures completed. As shown on Figure i, EAP operations can only be terminated after completing operations under Event Level 3 or 1. If an Event Level 2 is declared, the operations must be designated Event Level 3 or 1 before terminating the EAP operations.

#### 4.1 TERMINATION RESPONSIBILITIES

EAP operations will be terminated by the Engineering Director (or designee) after it is agreed that either the operations have been completed (Event Level 1 or 3) or that it is necessary to change the Event Level (Event Level 2). Termination of an Event Level 3 must include written approval of the On-Call Engineer. Additionally, a report must be prepared to document the evaluation of the problem causing the need for the implementation of the EAP and the details of all actions taken to remediate the situation that resulted in the implementation of the EAP.

In the case of Event Level 1, termination can be accomplished by the Engineering Director and must include the specific actions taken to ensure the safety of people and property downstream. Do not terminate the EAP unless it is certain that there is no further threat.

#### 4.2 FOLLOW-UP

Follow-up activities will be implemented to achieve the following general objectives:

#### Event Level 3 (Review to be completed within 90 days of termination)

- Review the existing EAP with all parties that participated in the EAP activities,
- Document any EAP procedures that were followed effectively,
- Document any ways that the EAP could be improved, and
- Insert this EAP Follow-up Report into Appendix B of the EAP.

#### **Event Level 2**

Should Event Level 2 be reached, but then changed to and terminated as an Event Level 3, the follow-up activities shall comply with those required for an Event Level 1 termination.

## Event Level 1 (Review to be completed within 180 days of termination)

- Review the existing EAP with all parties that participated in the EAP activities,
- Document any EAP procedures that were followed effectively,
- Document any ways that the EAP could be improved,
- Brainstorm, document, and implement actions to prevent recurrence of the problem that caused the implementation of the EAP, and
- Insert this EAP Follow-up Report into Appendix B of the EAP.



# SECTION 5. MAPS, FIGURES, AND SUPPORTING DATA

Copies of the following maps and figures are provided in this EAP for use in training personnel and during EAP operations.

- Figure 5.1 Location and Vicinity Map
- Figure 5.2 Ash Pond System Layout Annotated Aerial Photograph
- Figure 5.3 Emergency Site Access Route Map
- Figure 5.4 Estimated Dike Breach Inundation Map
- Figure 5.5 Ash Pond System Area and Capacity Curves



## **APPENDIX A**

Warning and Evacuation

This appendix is available for inserting local warning and evacuation plans developed by the Warning/Evacuation branch.



# APPENDIX B

Inundation Map Documentation



#### APPENDIX B

#### **Inundation Map Documentation**

The estimated flood inundation extent that could occur as a result of a dike breach at the Harding Street Generating Station Ash Pond System is presented on Figure 5.4 – Estimate Dike Breach Inundation Map. The Inundation Map includes flood wave traveling information including peak arrival time, maximum water elevation, incremental rise, peak dam breach flow, time to peak, and inundation duration for various locations on the map. The transparent orange and blue colored areas shown on Figure 5.4 represent the estimated maximum flood inundation extent. The areas of the map highlighted in transparent orange color represent an Immediate Impact Area and includes Lick Creek and other low lying areas of the generating station adjacent to Lick Creek. The Immediate Impact Area has a very short flood wave arrival time (< 5 minutes) and the peak incremental water level rise can be significant; therefore, it is imperative that this area receive, if at all possible, preemptive warning of a potential dike breach should an incident or emergency event ever occur. The Dike Breach Inundation Areas represented by the transparent blue color are located further downstream from the Ash Pond System and are principally contained within natural water channels. Although, the water level is expected to temporarily rise as a result of a dike failure at the Ash Pond System, the peak incremental rise and flood wave arrival time are less critical. The flood wave arrival time is expected to be less than 30 minutes at the Interstate 465 Bridge over the White River, which is approximately 2 miles downstream of the Ash Pond System.

As a result of this inundation study, the maximum flood extent that could occur as a result of a dike breach at the Ash Pond System was determined to be always within the USGS flood inundation map boundary as determined from the USGS Scientific Investigation Report 2015-5051. In other words, flooding that may be caused by a dike breach is expected to remain within the river's flood plain and will not overtop the river's levee system already in place. This study also determined that no residential areas and critical infrastructure are located within the inundation area between the Ash Pond System and the Interstate 465 Bridge over the White River.

Detailed back-up calculations that were used to develop the inundation map, including all assumptions, references, and supporting documents, can be reviewed upon request at the Harding Street Generating Station EAP office.

#### **Basis and Assumptions**

- 1) A two-dimensional hydrodynamic model (ADCIRC) was used to compute the maximum dike breach flood extent.
- 2) Dike breach scenarios were developed using pond geometry information, dike slope stability analysis, and soil boring data.
- 3) Since Former Ponds 2, 4, 4A, and 4B were regraded in the fall of 2015 such that they no longer impound water, they are not included in the dike breach scenarios.
- 4) Cascading failure scenarios were developed based on engineering judgment, considering a combination of physically possible and realistic dike failure modes (i.e., hydrologic and non-hydrologic) of each active pond. Conservatively, a scenario considering simultaneous failure of all active ponds was also evaluated.



- 5) Wet ash inside the pond is conservatively considered as an equivalent volume of water.
- 6) Final inundation map was developed enveloping the flooding extents from the hydraulic analyses for the dike breach scenarios.



### **APPENDIX C**

Past EAP Activity

This appendix is the placeholder for copies of past EAP activity reports, Annual Review Verification Statements that must be completed after the annual review is performed, and Periodic Test Memos to be included after periodic tests have been performed.



# APPENDIX D

**EAP Review and Revision** 



#### APPENDIX D

EAP Review and Revision

#### **EAP Annual Review Meetings**

The annual review of the EAP for evaluation of consistency with plant operations and available resources will be conducted by the EAP Coordinator and reviewed by the Engineering Director. All changes noted will be made to the EAP as required and any needed training will be provided. Note that an EAP Annual Review Verification Statement shall be completed upon conclusion of the review.

An annual meeting will be held for all EAP personnel included on the EAP distribution list in Appendix E to refresh themselves on the content of the EAP and to review the conduct of all EAP events that may have occurred. In the event that an Event Level 1 occurs, EAP personnel will meet immediately after the termination of the event to assess important aspects of this event and make all changes necessary to decrease the risk of future occurrences.

#### Revision

The EAP Coordinator will be responsible for ensuring that the EAP documents are revised. After changes are made, a new EAP with updated information will be sent to all holders with clear and prominent instructions to destroy the outdated copy in their files. The new EAP will be certified by a professional engineer registered in the State of Indiana in accordance with 40 CFR 257.73(a)(3)(iv). At least once annually, the EAP Coordinator will perform an audit of the EAP copies to ensure that all principal members of the organization have the correct copies in their possession.



# FORM D.1

Ash Pond System – EAP Annual Review Verification Statement

Name of Dike: Harding Street Generating Station - Ash Pond System				
Date of Drill:				
<ul> <li>A. The current EAP is on hand and all revisions have been inserted.</li> <li>B. The readiness evaluated in the drill was acceptable.</li> <li>C. The communications network is correct and was verified.</li> <li>D. The training of personnel is sufficient and acceptable.</li> <li>E. The EAP Annual Review procedures were followed.</li> </ul>				
Additional Comments:				
(individual responsible for conducting EAP Annual Review)	Date			
(printed name)				
(EAP Coordinator)	Date			
(printed name)				



# APPENDIX E

**EAP Distribution** 



# **APPENDIX E** EAP Distribution

Name	Title	Contact Information	EAP Copy No.
Juan Hummel	EAP Coordinator		1
Jason Deadmond	EAP Engineering Director		2
Brandon Daugherty	Alternate EAP Engineering Director		3
Claire Dalton	EAP Public Relations		4
Brandi Davis- Handy	Alternate EAP Public Relations	Contact information for emergency action personnel are on file with the appropriate station	5
Marion County Public Health Department	EAP Warning/Evacuation Director	personnel.	6
Dave Hendron	EAP On-Call Engineer		7
Rick Jacobs	Alternate EAP On-Call Engineer		8
Mark Holbrook	IPL Harding Street Generating Station Plant Manager		9
			10
			11
			12
			13
			14



#### **APPENDIX F**

Location of Supplementary Information

This appendix contains background information and pertinent data, and is also the place holder for any other key supplementary information such as emergency materials, service contracts, and any other relevant material for the Harding Street Ash Pond System and other similar information that may be placed in this appendix by individual plan holders for quick reference during an event.



# APPENDIX G

Glossary



### APPENDIX G

Glossary

<u>Abutment:</u> The undisturbed natural material of the valley side against which a dike is constructed. The left and right abutments are defined as being on the right and left side of an observer looking downstream.

<u>Appurtenant structure:</u> A structure necessary for the operation of a dike, such as outlets, trash racks, valves, spillways, power plants, tunnels, etc.

<u>Breach:</u> An eroded opening through a dike that drains the reservoir. A controlled breach is a constructed opening. An uncontrolled breach is an unintentional opening that allows uncontrolled discharge from the reservoir.

<u>Channel:</u> A general term for any natural or artificial watercourse.

<u>Conduit:</u> A closed channel to convey water through, around, or under a dike.

Crest of Dike: Top of dike.

<u>Cross section:</u> A sectional view of a dike formed by passing a plane through the dike perpendicular to its axis.

<u>Dike</u>: A structure constructed of earth or coal combustion residual (CCR) materials intended to retain fluid and solid materials as part of CCR processing operations for the Harding Street Generating Station.

Dike failure: The uncontrolled release of reservoir contents.

<u>Drain, toe:</u> A system of pipes and/or pervious material along the downstream toe of a dike used to collect seepage from the foundation and embankment and convey it to a free outlet.

Drainage area: The area that drains to a particular point of a river or stream.

<u>Drawdown:</u> The difference between a water level and a lower water level in a reservoir within a particular time. Used as a verb, it is the lowering of the water surface due to release of water from the reservoir.

<u>EAP Operations</u>: All actions taken by Harding Street Generating Station and other involved parties to address an incident or emergency event.

<u>Earthquake:</u> A sudden motion or trembling in the earth caused by the abrupt release of accumulated stress along a fault.

<u>Emergency Action Plan (EAP):</u> A comprehensive, single-source document providing accurate and current instructions intended to help Harding Street Generating Station and IPL save lives, minimize property damage, and minimize environmental impacts caused by large releases from a dike failure at the Harding Street Ash Pond System, or other events that present hazardous conditions.



<u>Emergency Event:</u> An event which takes place or a condition which develops that is of a serious nature that may endanger the dike, or endanger persons or property, and demands immediate attention.

<u>Flood:</u> A temporary rise in water levels resulting in inundation of areas not normally covered by water; may be expressed in terms of probability of exceedance per year such as one percent chance flood or expressed as a fraction of the probable maximum flood or other reference flood. Some related terms are:

- a. <u>Flood, Inflow Design (IDF):</u> That flood used in the design of a safe dike and its appurtenant works particularly for sizing the spillway and outlet works, and for determining maximum temporary storage and height of dike requirements.
- b. <u>Flood, Probable Maximum (PMF):</u> The maximum runoff condition resulting from the most severe combination of hydrologic and meteorological conditions that are considered reasonably possible for the drainage basin under study.

Freeboard: Vertical distance between a stated water level and the top of dike.

<u>Height, maximum hydraulic:</u> The vertical distance between the maximum design water level and the lowest point in the original streambed.

<u>Height, structural:</u> The vertical distance between the lowest point on the dike crest and the lowest point of the excavated foundation.

Hydrograph, breach or dike failure: A flood hydrograph resulting from a dike breach.

<u>Hydrograph, flood:</u> A graphical representation of the flood discharge with respect to time for a particular point on a stream or river.

<u>Hydrograph, unit:</u> A hydrograph with a volume of one inch of runoff resulting from a storm of a specified duration and aerial distribution. Hydrographs from other storms of the same duration and distribution are assumed to have the same time base but with ordinates of flow in proportion to the runoff volumes.

<u>Incident:</u> An unusual event which takes place, or a condition which is slowly developing, that is not normally encountered in the routine operation of the Ash Pond System, or necessitates a variation from the operating procedures. Such events are more common than emergency conditions and often offer time to conduct preplanned responses to the slowly developing situation. If addressed in a timely manner, such events can often be prevented from progressing into a much worse event.

<u>Incident Command System (ICS):</u> A management system designed to control personnel, equipment, supplies, and communications at the scene of an unusual or emergency event. An Incident Command System is typically deployed at the beginning of an event until the management of the on-scene



operations are no longer needed. The structure of the Incident Command System can be expanded or contracted depending on the changing needs of the event. The Incident Command System allows all involved parties to effectively communicate using common terminology.

<u>Instrumentation:</u> An arrangement of devices installed into or near dikes (piezometer and staff gauge at the Harding Street Ash Pond System) that provide measurements that can be used to evaluate performance parameters of a structure.

<u>Inundation map:</u> A map delineating the area that would be submerged by a particular flood event.

<u>Length of dike</u>: The length along the top of the dike between contact abutments. This also includes the spillway, power plants, navigation lock, fish pass, etc., where these form part of the length of the dike. If detached from the dike, these structures should not be included.

Outlet: An opening through which water can be discharged.

<u>Phreatic surface</u>: The free surface of water seeping at atmospheric pressure through soil or rock.

<u>Piezometer:</u> An instrument for measuring water or pressure head.

<u>Piping:</u> The progressive development of internal erosion by seepage appearing downstream as a hole or seam discharging water containing soil particles.

Probability: The likelihood of an event occurring within a given period of time.

<u>Probable Maximum Precipitation (PMP):</u> Theoretically, the greatest depth of precipitation for a given duration that is physically possible over a given size storm area at a particular geographical location.

Reservoir: A body of water impounded by a dike in which water can be stored.

<u>Reservoir surface area:</u> The area covered by a reservoir when filled to a specified level.

<u>Riprap:</u> A layer of stone, precast blocks, bags of cement or other suitable material, generally placed on the upstream slopes of an embankment or along a watercourse as protection against wave action, erosion, or scour. It consists of pieces of relatively large size as distinguished from a gravel blanket.

<u>Seepage</u>: Flow or movement of water through a dike, its foundation, or its abutments.

<u>Slope:</u> Inclination from the horizontal, measured as the ratio of horizontal units to corresponding vertical units.



<u>Spillway:</u> A structure over or through which flow is discharged from a reservoir. If the rate of flow is controlled by mechanical means such as gates, it is considered a controlled spillway. If the elevation of the spillway crest is the only control, it is considered an uncontrolled spillway.

<u>Spillway channel:</u> An open channel or closed conduit conveying water from the spillway inlet downstream.

<u>Spillway crest:</u> The lowest level at which water can flow over or through the spillway.

<u>Spillway</u>, chute: An inclined channel, usually separate from the dike, to convey reservoir overflow into the natural channel below the dike or into an adjacent natural drainage channel.

<u>Storage</u>: The retention of water or delay of runoff either by planned operation, as in a reservoir, or by temporary filling of overflow areas, as in the progression of a flood wave through a natural stream channel. Definitions of specific types of storage in reservoirs are:

- a. <u>Dead Storage:</u> The reservoir volume between the invert of the lowest discharge and the reservoir bottom.
- b. <u>Active Storage:</u> The reservoir volume between the normal reservoir water surface elevation and the invert of the lowest discharge.
- c. <u>Flood Storage:</u> The reservoir volume between the crest of the dike and the normal reservoir water surface elevation.